BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2014-15/OW/WORK_INDENT16496/CALL-

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/10/2014-15, Date: 21.02.2015

Construction of dry waste collection and sorting centre at Sahakarangara in ward no. 08, Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MURALI MOHAN Y V	
				In Figures	In Words
1	45	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications	cum	140.0	Rupees One Hundred Forty Only
2	25.34	KSRB 2-2.2 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	cum	250.0	Rupees Two Hundred Fifty Only
3	7.53	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications,	cum	5100.0	Rupees Five Thousand One Hundred Only
4	7.97	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing complete as per specifications	cum	3750.0	Rupees Three Thousand Seven Hundred Fifty Only
5	5.97	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification	cum	4450.0	Rupees Four Thousand Four Hundred Fifty Only
6	5.61	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications	cum	5950.0	Rupees Five Thousand Nine Hundred Fifty Only

7	0.504	KSRB 4.9.2:Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	qtl	76900.0	Rupees Seventy Six Thousand Nine Hundred Only
8	6.64	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specification	cum	69.0	Rupees Sixty Nine Only
9	16.25	KSRB 2.5 : Earthwork excavation(in deposited soil) and filling sides of foundation upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layer by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications	cum	230.0	Rupees Two Hundred Thirty Only
10	1.53	Providing and fabricating structrual steel truss work including 2 coats of enamel paint over a coat of shop paint to design, drawing furnished by the consultant	MT	90000.0	Rupees Ninety Thousand Only
11	90.25	Providing metacolour sheet roofing including accoustic treatment etc complete as per detail drawing furnished by the consultant	Sqm	1020.0	Rupees One Thousand Twenty Only
12	26.9	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	Sqm	970.0	Rupees Nine Hundred Seventy Only
13	6.5	KSRB: 7.5 Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & operations complete Including pulling hooks, 4nos handles wit hall fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m	Sqm	2800.0	Rupees Two Thousand Eight Hundred Only
14	3	KARB 7.6 Providing and fixing top covers made out of 20 guage M.S. sheet over m pull and push rolling shutters bent to shape including cost of red lead primer coat of painting, materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m	m	640.0	Rupees Six Hundred Forty Only
15	168	KSRB 7.9 : Providing and fixing M.S. grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications.	kg	98.0	Rupees Ninety Eight Only

16	.1	KSRB 15.3.9: Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specification	Sqm	180.0	Rupees One Hundred Eighty Only
17	28.1	KSRB 15-16.1: providing and finishing external walls in two coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications	Sqm	75.0	Rupees Seventy Five Only
18	3.25	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5750.0	Rupees Five Thousand Seven Hundred Fifty Only
19	32.49	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift	Sqm	90.0	Rupees Ninety Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92